BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Providing granite Benches in ward no-04

Agency:-m/s KRIDL

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
1	368.85	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no141,PWD SR 2016-17)	Cum	96.48	Rupees Ninety Six And Paise Forty Eight Only
2	368.85	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2016-17)	Cum	68.00	Rupees Sixty Eight Only
3	310.72	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications including cost of gravell/murrum,watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (Page No. 148 & Item No. 19.60)	Cum	355.33	Rupees Three Hundred Fifty Five And Paise Thirty Three Only
4	96.86	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no: KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2016-17)	Cum	5726.51	Rupees Five Thousand Seven Hundred Twenty Six And Paise Fifty One Only

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 016

Executive Engineer
Project Division
Yelahanka Zone

Sl No	Ap... Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
5	16.00	KSRB5.2.2: Providing and constructing granite/trap/basalt **size stone masonry** in foundation with cement mortor 1:8,stone hammer dressed in courses less than 20 cms high.bond stones at 2 m apart in each course, including cost of all materials ,labour, curing complete as per specification. No. KBS 5.1.13 (PWD, S.R. 2016-17)(Page No. 23, item No. 5.5)	Cum	4749.93	Rupees Four Thousand Seven Hundred Forty Nine And Paise Ninety Three Only
6	188.13	KSRB 5-14 : Providing and constructing **load bearing wall with solid concrete blocks** having block density not less than 1800kg/cum having a minimum average compressive strength of 4.00N/mm2 confirming to IS 2185(Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding , curing , hire charges of machineries etc., complete as per specfications . KBS No.5.4 with solid concrete blocks of size 40x15x20cm (PWD, S.R. 2016-17)(Page No. 25, item No. 5.27.2)	Sqm	977.75	Rupees Nine Hundred Seventy Seven And Paise Seventy Five Only
7	77.09	KSRB M2200-5.11.Design mix M20 with OPC cement @320 kgs,with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999 Reaffirmed-2008.etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no216,sno28.7.9)	Cum	8413.87	Rupees Eight Thousand Four Hundred Thirteen And Paise Eighty Seven Only
8	793.93	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mm. (pwd sr2016-17,p.no109,sno14.61.1)	Sqm	2222.60	Rupees Two Thousand Two Hundred Twenty Two And Paise Sixty Only
9	60.00	Executive Bench- Made out of Sadarahalli Grey stone with Hand supports with 3 line finishing with arch design with 100mm slabs .Height 90xLength 150 width 45cms (Data appoved rate)	Nos	18200.00	Rupees Eighteen Thousand Two Hundred Only

23/3/18

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 016

Contractor

Executive Engineer
Project Division
Yelahanka Zone